

PA Game Commission – Rainetown Road



Problem: Wetlands are on both sides of the road. Water from one side occasionally overtopped the road, which caused erosion and carried sediment into the wetland on the opposite side. The elevation of an existing overflow pipe was too high and was in an unfavorable location.

Solution: – A 36” squash pipe was installed as a stream crossing. Two 24” overflow pipes were installed in better locations. Headwalls and endwalls were built as well as a 360’ French Mattress. Two turnouts were installed. 621 tons of road fill were placed to raise the road profile. Disturbed areas were seeded and mulched as needed.

