

Young Township – Cunningham Road Project

This is a Low Volume Road (LVR) Project.



Problem: Stormwater from the top of the hill was running down the unstable berms of the paved road, causing the berms to erode. Sediment washed into inlets and plugged the existing pipes. The tail wall of an existing stream crossing was not adequate.

Solution: Berms were widened to 4 feet and paved with a curb. Sediment was removed from the inlets and the plugged pipes. A new tail wall was constructed.

